



June 23, 2023

La Trinidad United Methodist Church
300 San Fernando
San Antonio, Texas 78207

REFURBISH EXISTING SIGN AND INSTALL AT PRIOR LOCATION

1. Existing sign that has been in storage since removal will be cleaned. Metal frame will be primed and painted.
2. Remove previous marquee and install new marquee illuminated per photo-one side only.
3. Above the marquee, install metal lettering for name of church and illuminate with 60 watt lighting.
4. Set frame in concrete and trim out in tile to match prior work on east side of building.
5. Mount bronze dedication pack below marquee.

Accu-Rite Roofing and Construction Services

4709 ROOSEVELT AVENUE SAN ANTONIO, TEXAS 78214 (210) 227-6807 FAX (210) 227-0418

Please visit our website at: www.accuriteroof.com



June 23, 2023

La Trinidad United Methodist Church
300 San Fernando
San Antonio, Texas 78207

SPECIFICATIONS OF MATERIAL TO BE USED

1. DTM primed for metal frame.
2. DTM semi-gloss paint for frame.
3. Marque pre-finished galvalume metal white backing.
4. Lettering black metal.
5. 12" x 6" terracotta tile glazed at lower flower bed.
6. Ready mix concrete to set and back fill.
7. Cylinder lighting LED 60 watt.



NORTH ELEVATION





EAST ELEVATION

SOUTH ELEVATION



WEST ELEVATION