

ESTIMATE

Amigos Ironworks
78233

amber@amigosfabrication.com
+1 (210) 531-6338



Bill to
Sherry Hess
711 Matagorda St
San Antonio, Tx

Ship to
Sherry Hess
711 Matagorda St
San Antonio, Tx

Estimate details

Estimate no.: 1041
Estimate date: 03/10/2025

#	Product or service	Description	Qty	Rate	Amount
1.	Fence Fabrication	Fabrication and installation of exterior panel fencing. Constructed of 2x2 sq tubing posts with 2x1 top and bottom rail. Framework will picture frame cattle panel with 4x4 squares. Cattle panel will be left in original galvanized finish and framework steel will be cleaned and sprayed with a solution to create rust effect before prepping and clear coating surface. This will prevent rust from continuing as well as rust transfer to homeowner. All posts will be set 24' or deeper unless concrete restricts depth. Top rail will be flush and continuous with no caps (as discussed in meeting). All end caps will be welded, not plastic. Post width will be 8' or as close to 8' to create equal spans.	105	\$95.00	\$9,975.00
2.	Gate Fabrication	Fabrication and installation of rolling driveway gate on track and wheels. Design will match that of fence with same paneling and 2x2, 2x1 framework. Finished in rust and clear coat. Half of gates track will be attached to driveway and half will be suspended and attached to posts set in ground. Driveway gate will be manual with no motor and lockable latch for security.	12	\$185.00	\$2,220.00
3.	Gate Fabrication	Fabrication and installation of walk-through gate with the same design and finish as fence and driveway gate. Gate will hinge from the left side post as you're walking towards the house from the street and hinge out towards street. Gate will be fitted	5	\$145.00	\$725.00

with a lockable latch for homeowner to
secure at night.

4. Demo of existing fence and gates	Demolition and removal of existing wooden fence posts and paneling from site.	1	\$900.00	\$900.00
--	--	---	----------	----------

Total **\$13,820.00**

Accepted date

Accepted by